Hydraulic Crawler Crane

CKS

1100

Model : CKS1100

Max. Lifting Capacity: **110 t x 3.6 m ***
Max. Crane Boom Length: **70.1 m**
Max. Fixed Jib Combination: **61.0 m + 21.3 m**

* Auxiliary sheave is necessary.



KOBELCO

CKS1100
CONTENTS

SPECIFICATIONS

Power Plant

Model: HINO J08E-VM
Type: 4 cycle, water-cooled, vertical in-line 6, direct injection, turbo-charger, intercooler
Displacement: 7,684 liters
Rated power: 213 kW/2,100 min^{-1}
Max. Torque: 1,017 N·m/1,600 min^{-1}
Cooling System: Water-cooled
Starter: 24V-5kW
Radiator: Corrugated type core, thermostatically controlled
Air cleaner: Dry type with replaceable paper element
Throttle: Twist grip type hand throttle, electrically actuated
Fuel filter: Replaceable paper element
Batteries: Two 12V x 136 Ah/5HR capacity batteries, series connected
Fuel tank capacity: 400 liters

Hydraulic System

Main pumps: 4 variable displacement piston pumps
Control: Full-flow hydraulic control system for infinitely variable pressure to all winches, propel and swing. Controls respond instantly to the touch, delivering smooth function operation.
Cooling: Oil-to-air heat exchanger (plate-fin type)
Filtration: Full-flow and bypass type with replaceable element
Max. relief valve pressure:
Load hoist, boom hoist and propel system: 31.9 MPa
Swing system: 27.5 MPa
Control system: 5.4 MPa
Hydraulic Tank Capacity: 535 liters

Boom Hoisting System

Powered by a hydraulic motor through a planetary reducer.
Brake: A spring-set, hydraulically released multiple-disc brake is mounted on the boom hoist motor and operated through a counter-balance valve.
Drum Lock: External ratchet for locking drum
Drum: Single drum, grooved for 20 mm dia. wire rope
Line Speed: Single line on first drum layer
Hoisting/Lowering: 48 to 2 m/min
Boom hoisting/lowering: 20mm x 155 m
Boom guy line: 34 mm
Boom backstops: Required for all boom length

Load Hoisting System

Front and rear drums for load hoist powered by a hydraulic variable plunger motors, driven through planetary reducers.
Negative Brake: A spring-set, hydraulically released multiple-disc brake is mounted on the hoist motor and operated through a counter-balance valve. (Positive free fall brake is optional)
Drum Lock: External ratchet for locking drum
Drums:
Front Drums:
614 mm P.C.D x 617 mm wide drum, grooved for 26 mm wire rope. Rope capacity is 265 m working length and 360 m storage length.
Rear Drum: 614 mm P.C.D x 617 mm, grooved for 26 mm wire rope. Rope capacity is 235 m working length and 360 m storage length.
Diameter of wire rope
Main winch: 26 mm x 265 m
Aux. winch: 26 mm x 235 m
Third winch: 26 mm x 190 m
Line Speed*:
Hoisting/lowering: 120 to 3 m/min
Line Pull:
Max. Line Pull*: 208 kN {21.2 tf}
(Referential performance)
Rated Line Pull: 108 kN {11.0 tf}
*Single line on first drum layer

Swing System

Swing unit is powered by hydraulic motor driving spur gears through planetary reducer, the swing system provides 360° rotation.
Swing parking brakes: A spring-set, hydraulically released multiple-disc brake is mounted on swing motor.
Swing circle: Single-row ball bearing with an integral internally cut swing gear.
Swing lock: Manually, four position lock for transportation
Swing Speed: 3.2 min^{-1} (rpm)

Upper Structure

Torsion-free precision machined upper frame. All components are located clearly and service friendly. Engine will with low noise level.
Counterweight: 34.6 ton

Cab & Control

Totally enclosed, full vision cab with safety glass, fully adjustable, high backed seat with a headrest and armrests, and intermittent wiper and window washer (skylight and front window).
Cab fittings:
Air conditioner, convenient compartment (for tool), cup holder, cigarette lighter, sun visor, roof blind, tinted glass, floor mat, footrest, and shoe tray

Lower Structure

Steel-welded carbody with axles. Crawler assemblies can be hydraulically extended for wide-track operation or retracted for transportation. Crawler belt tension is maintained by hydraulic jack force on the track-adjusting bearing block.
Carbodyweight: 6.5 ton
Crawler drive: Independent hydraulic propel drive is built into each crawler side frame. Each drive consists of a hydraulic motor propelling a driving tumbler through a planetary gear box. Hydraulic motor and gear box are built into the crawler side frame within the shoe width.
Crawler brakes: Spring-set, hydraulically released parking brakes are built into each propel drive.
Steering mechanism: A hydraulic propel system provides both skid steering (driving one track only) and counter-rotating steering (driving each track in opposite directions).
Track rollers: Sealed track rollers for maintenance-free operation.
Shoe (flat): 900 mm wide each crawler
Max. gradeability: 40%

Weight

Including upper and lower machine, 34.6 ton counterweight and 6.5 ton carbody weight, basic boom (or basic boom + basic jib), hook, and other accessories.
Weight: 102 ton
Ground pressure: 95.4 kPa

Attachment

Boom & Jib:
Welded lattice construction using tubular, high-tensile steel chords with pin connection between sections.

Boom and Jib length

	Min. Length (Min. combination)	Max. Length (Max. combination)
Crane Boom	15.2 m	70.1 m
Fixed Jib	27.4 m + 9.1 m	61.0 m + 21.3 m

Main Specifications (Model: CKS1100)

Crane Boom	
Max. Lifting Capacity	110 t x 3.6 m *3
Max. Length	70.1 m
Fixed Jib	
Max. Lifting Capacity	10.9 t x 22.0 m
Max. Combination	61.0 m + 21.3 m
Main & Aux. Winch	
Max. Line Speed (1st layer)	120 m/min
Rated Line Pull (Single line)	108 kN {11.0 tf}
Wire Rope Diameter	26 mm
Wire Rope Length	265m (Main), 235 m (Aux.)
Brake Type (free fall)	Wet-type multiple disc brake (Optional)
Working Speed	
Swing Speed	3.2 min^{-1}{rpm}
Travel Speed	1.4/1.0 km/h
Power Plant	
Model	HINO J08E-VM
Engine Output	213 kW/2,100min^{-1}
Fuel Tank	400 liters

Hydraulic System	
Main Pumps	4 variable displacement
Max. Pressure	31.9 MPa {325 kgf/cm^2}
Hydraulic Tank Capacity	535 liters
Self-Removal Device	
	counterweight/crawler self-removal device
Weight	
Operating Weight	102 t *1
Ground Pressure	95.4 kPa
Counterweight	34,600 kg
Transport Weight	57,410 kg *2

Units are SI units. { } indicates conventional units.
Line speeds in table are for light loads. Line speed varies with load.
*1 Including upper and lower machine, 34.6 ton counterweight, 6.5 ton carbody weight, basic boom, hook, and other accessories.
*2 Base machine with boom base, gantry, crawlers, and wire ropes (front/boom hoist)
*3 Auxiliary sheave is must.

GENERAL DIMENSIONS

(Unit: mm)



This catalog may contain photographs of machines with specifications, attachments and optional equipment.

Limit of Hook Lifting



Hook	L
110 t hook	4.2 m
70 t hook	4.1 m
35 t hook	3.9 m



Hook	L'
Ball hook	3.6 m
35 t hook	3.9 m

BOOM AND JIB ARRANGEMENTS

Crane Boom Arrangements

Boom length m (ft)	Boom arrangement
15.2 (50)	
18.3 (60)	※ 
21.3 (70)	※ 
24.4 (80)	※ 
27.4 (90)	※ 
30.5 (100)	※ 
33.5 (110)	※ 
36.6 (120)	※ 
39.6 (130)	※ 
42.7 (140)	※ 
45.7 (150)	※ 

Boom length m (ft)	Boom arrangement
48.8 (160)	※ 
51.8 (170)	※ 
54.9 (180)	※ 
57.9 (190)	※ 
61.0 (200)	※ 
64.0 (210)	※ 
67.1 (220)	※ 
70.1 (230)	※ 

Symbol	Boom Length	Remarks
B	7.6 m	Boom Base
T	7.6 m	Boom Top
10	3.0 m	Insert Boom
20	6.1 m	Insert Boom
40	12.2 m	Insert Boom
40A	12.2 m	Insert Boom with lug

↗ mark shows the boom insert with lug attached and the guy line installing position when the fixed jib is used.

※ mark shows the standard boom arrangement which make the boom arrangement of less than the each boom length possible.

○ mark shows the installing of the cable roller for the insert boom.

Fixed Jib Arrangements



Crane boom length	Jib length m (ft)	Jib arrangement
27.4 m ～ 61.0 m	9.1 (30)	
	12.2 (40)	
	15.2 (50)	
	18.3 (60)	
	21.3 (70)	

Symbol	Jib Length	Remarks
B	4.6 m	Jib Base
T	4.6 m	Jib Top
10	3.0 m	Insert Jib
20	6.1 m	Insert Jib

Crane Boom


82°
75°
70°
65°
60°
55°
70.1m Boom
67.1m Boom
64.0m Boom
61.0m Boom
57.9m Boom
54.9m Boom
51.8m Boom
48.8m Boom
45.7m Boom
42.7m Boom
39.6m Boom
36.9m Boom
33.5m Boom
30.5m Boom
27.4m Boom
24.4m Boom
21.3m Boom
18.3m Boom
15.2m Boom
50°
45°
40°
35°
30°
25°
75
70
65
60
55
50
45
40
35
30
25
20
10
15
20
25
30
35
40
45
50
55
Height above ground (m)
Radius from center of rotation (m)
2.2m
Center of rotation
1.1m

Fixed Jib 10°


80°
10°
61.0m Boom + 21.3m Jib
61.0m Boom + 18.3m Jib
61.0m Boom + 15.2m Jib
61.0m Boom + 12.2m Jib
61.0m Boom + 9.1m Jib
27.4m Boom + 21.3m Jib
27.4m Boom + 18.3m Jib
27.4m Boom + 15.2m Jib
27.4m Boom + 12.2m Jib
27.4m Boom + 9.1m Jib
85
80
75
70
65
60
55
50
45
40
35
30
25
20
Height above ground (m)
10
15
20
25
30
35
40
45
50
55
Radius from center of rotation (m)
2.2m
Center of rotation
1.1m

Fixed Jib 30°


80°
30°
61.0m Boom + 21.3m Jib
61.0m Boom + 18.3m Jib
61.0m Boom + 15.2m Jib
61.0m Boom + 12.2m Jib
61.0m Boom + 9.1m Jib
27.4m Boom + 21.3m Jib
27.4m Boom + 18.3m Jib
27.4m Boom + 15.2m Jib
27.4m Boom + 12.2m Jib
27.4m Boom + 9.1m Jib
85
80
75
70
65
60
55
50
45
40
35
30
25
20
Height above ground (m)
10
15
20
25
30
35
40
45
50
55
Radius from center of rotation (m)
2.2m
Center of rotation
1.1m

SUPPLEMENTAL DATA

- Ratings according to EN13000.
- Operating radius is the horizontal distance from centerline of rotation to a vertical line through the center of gravity of the load.
- Deduct weight of hook block (s), slings and all other load handling accessories from main boom ratings shown.
- Ratings shown are based on freely suspended loads and make no allowance for such factors as wind effect on lifted load, ground conditions, out-of-level, operating speeds or any other condition that could be detrimental to the safe operation of this equipment.
  The operator, therefore, has the responsibility to judge the existing conditions and reduce lifted loads and operating speeds accordingly.
- Ratings are for operation on a firm and level surface, up to 1 % gradient.
- At radii and boom lengths where no ratings are shown on chart, operation is not intended nor approved.
- Boom inserts and guy lines must be arranged as shown in the "operator's manual".
- Boom hoist reeving is 10 part line.
- Gantry must be in raised position for all conditions.
- Boom backstops are required for all boom lengths.
- The boom should be erected over the front of the crawlers, not laterally.
- Ratings inside of boxes ☐ are limited by strength of materials.
- The minimum rated load is 1.5 (Ton).
- Crawler frames must be fully extended for all crane operations.

(Crane boom lifting)

- The total load that can be lifted is the value for weight of main hook block, slings, and all other load handling accessories deducted from crane boom ratings shown.

(Fixed jib lifting)

- The total load that can be lifted is the value for weight of jib hook block, slings, and all other load handling accessories deducted from fixed jib ratings shown.
- The availability of fixed jib mounting
  - On crane boom : Range 27.4 m to 61.0 m.

<Reference Information>

Main hoist loads

No. of Parts of Line	1	2	3	4	5
Maximum Loads (kN)	108	216	324	431	539
Maximum Loads (t)	11.0	22.0	33.0	44.0	55.0

No. of Parts of Line	6	7	8	9	10
Maximum Loads (kN)	647	755	863	971	1,079
Maximum Loads (t)	66.0	77.0	88.0	99.0	110.0

Auxiliary hoist loads

No. of Parts of Line	1	2
Maximum Loads (kN)	108	216
Maximum Loads (t)	11.0	22.0

Weight of hook block				
Hook Block	110 t	70 t	35 t	Ball Hook
Weight (t)	1.7	0.9	0.7	0.45

Operation of this equipment in excess of rated loads or disregard of instruction voids the warranty.

LIFTING CAPACITIES

Crane Boom Lifting Capacities

Counterweight: 34.6 t
Carbody Weight: 6.5 t

Unit: metric ton

Working radius (m) \ Boom length (m)	15.2	18.3	21.3	24.4	27.4	30.5	33.5	36.6	39.6	42.7	Boom length (m) \ Working radius (m)
3.5	3.6m/110.0										**3.5**
4.0	98.6	4.1m/95.3	4.6m/86.0								**4.0**
5.0	77.7	77.7	77.7	77.0	5.5m/66.0	5.9m/58.9					**5.0**
6.0	62.2	62.2	62.2	62.2	60.7	58.2	6.4m/52.4	6.8m/47.1			**6.0**
7.0	53.3	53.2	53.2	53.1	51.2	49.4	47.6	46.0	7.3m/42.7	7.8m/38.9	**7.0**
8.0	44.5	44.4	44.4	44.2	44.2	42.7	41.4	40.1	38.9	37.7	**8.0**
9.0	37.6	37.5	37.4	37.3	37.3	37.2	36.5	35.5	34.5	33.5	**9.0**
10.0	32.5	32.4	32.3	32.2	32.2	32.1	32.0	31.7	30.9	30.1	**10.0**
12.0	25.5	25.3	25.2	25.1	25.1	24.9	24.9	24.8	24.7	24.6	**12.0**
14.0	20.8	20.7	20.6	20.4	20.4	20.3	20.2	20.1	20.0	19.9	**14.0**
16.0	14.4m/20.1	17.4	17.3	17.1	17.1	16.9	16.9	16.7	16.7	16.6	**16.0**
18.0		17.1m/16.0	14.8	14.7	14.6	14.5	14.4	14.3	14.2	14.1	**18.0**
20.0			19.7m/13.2	12.8	12.7	12.6	12.5	12.4	12.3	12.2	**20.0**
22.0				11.3	11.2	11.1	11.0	10.8	10.8	10.6	**22.0**
24.0				22.4m/11.1	10.0	9.8	9.8	9.6	9.5	9.4	**24.0**
26.0					25.0m/9.5	8.8	8.7	8.6	8.5	8.4	**26.0**
28.0						27.6m/8.1	7.9	7.7	7.6	7.5	**28.0**
30.0							7.2	7.0	6.9	6.8	**30.0**
32.0							30.3m/7.1	6.4	6.3	6.1	**32.0**
34.0								32.9m/6.1	5.7	5.6	**34.0**
36.0									35.6m/5.3	5.1	**36.0**
38.0										4.7	**38.0**
40.0										38.2m/4.6	**40.0**
Reeves	10	9	8	7	6	6	5	5	4	4	**Reeves**

Working radius (m) \ Boom length (m)	45.7	48.8	51.8	54.9	57.9	61.0	64.0	67.1	70.1	Boom length (m) \ Working radius (m)
8.0	8.2m/35.6	8.7m/32.9								**8.0**
9.0	32.4	31.7	9.1m/30.4	9.6m/28.1						**9.0**
10.0	29.1	28.5	27.7	27.0	26.1	10.5m/22.0	10.9m/22.0	11.4m/19.1	11.9m/15.0	**10.0**
12.0	24.0	23.6	23.0	22.4	21.7	21.4	20.8	18.4	14.9	**12.0**
14.0	19.8	19.7	19.4	18.9	18.4	18.2	17.6	16.5	13.1	**14.0**
16.0	16.4	16.4	16.3	16.1	15.8	15.6	15.2	14.8	11.7	**16.0**
18.0	13.9	13.9	13.8	13.6	13.5	13.5	13.2	12.8	10.4	**18.0**
20.0	12.0	12.0	11.9	11.7	11.6	11.6	11.4	11.3	9.3	**20.0**
22.0	10.5	10.5	10.3	10.2	10.0	10.1	9.9	9.8	8.3	**22.0**
24.0	9.2	9.2	9.1	8.9	8.8	8.8	8.6	8.5	7.5	**24.0**
26.0	8.2	8.2	8.0	7.9	7.7	7.7	7.6	7.5	6.7	**26.0**
28.0	7.3	7.3	7.2	7.0	6.9	6.9	6.7	6.6	6.0	**28.0**
30.0	6.6	6.5	6.4	6.3	6.1	6.1	6.0	5.8	5.3	**30.0**
32.0	5.9	5.9	5.8	5.6	5.5	5.5	5.3	5.2	4.7	**32.0**
34.0	5.4	5.3	5.2	5.0	4.9	4.9	4.7	4.6	4.2	**34.0**
36.0	4.9	4.8	4.7	4.6	4.4	4.4	4.2	4.1	3.7	**36.0**
38.0	4.5	4.4	4.3	4.1	4.0	3.9	3.8	3.6	3.2	**38.0**
40.0	4.1	4.0	3.9	3.7	3.5	3.5	3.3	3.2	2.7	**40.0**
42.0	40.8m/4.0	3.7	3.5	3.3	3.2	3.1	2.9	2.8	2.3	**42.0**
44.0		43.5m/3.5	3.2	3.0	2.8	2.8	2.6	2.4	1.9	**44.0**
46.0			2.9	2.7	2.5	2.5	2.3	2.1	1.6	**46.0**
48.0			46.1m/2.9	2.4	2.2	2.2	2.0	1.8		**48.0**
50.0				48.8m/2.3	2.0	1.9	1.7	1.6		**50.0**
52.0					51.4m/1.8	1.7	1.5			**52.0**
54.0						1.5				**54.0**
Reeves	4	3	3	3	3	2	2	2	2	**Reeves**

Note:
Ratings according to EN13000.
Ratings shown in [ ] are determined by the strength of the boom or other structural components.
Lifting capacities may vary depending on hook used or with/without auxiliary sheave.
Please refer rated chart in operator's cabin.

Fixed Jib Lifting Capacities (Without Main Hook Block) (Jib Offset Angle : 10°)

Counterweight: 34.6 t
Carbody Weight: 6.5 t

Unit: metric ton

Boom length (m)	27.4					30.5					33.5					Boom length (m)
Jib length (m)	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	Jib length (m)
10.0	10.9					10.9										10.0
12.0	10.9	10.9	10.9			10.9	10.9	10.9			10.9	10.9				12.0
14.0	10.9	10.9	10.9	9.8	7.1	10.9	10.9	10.9	9.9	7.1	10.9	10.9	10.9	9.9		14.0
16.0	10.9	10.9	10.9	9.6	6.9	10.9	10.9	10.9	9.7	6.9	10.9	10.9	10.9	9.7	7.0	16.0
18.0	10.9	10.9	10.2	8.9	6.7	10.9	10.9	10.7	9.3	6.8	10.9	10.9	10.9	9.5	6.8	18.0
20.0	10.9	10.9	9.2	8.0	6.5	10.9	10.9	9.7	8.4	6.6	10.9	10.9	10.2	8.8	6.7	20.0
22.0	10.9	10.2	8.4	7.3	6.4	10.9	10.9	8.9	7.6	6.5	10.9	10.9	9.3	8.0	6.5	22.0
24.0	10.1	9.4	7.7	6.7	6.0	10.0	10.0	8.2	7.0	6.3	9.9	10.0	8.6	7.4	6.4	24.0
26.0	9.1	8.7	7.2	6.2	5.5	8.9	9.1	7.6	6.5	5.8	8.8	9.0	8.0	6.8	6.1	26.0
28.0	8.2	8.1	6.7	5.7	5.1	8.0	8.2	7.0	6.0	5.4	7.9	8.1	7.4	6.3	5.6	28.0
30.0	7.4	7.5	6.2	5.4	4.7	7.3	7.4	6.6	5.6	5.0	7.2	7.3	7.0	5.9	5.2	30.0
32.0	6.8	6.9	5.9	5.0	4.4	6.6	6.7	6.2	5.3	4.7	6.5	6.6	6.5	5.6	4.9	32.0
34.0		6.3	5.5	4.7	4.2	6.1	6.2	5.9	5.0	4.4	6.0	6.1	6.1	5.3	4.6	34.0
36.0			5.3	4.5	3.9		5.7	5.6	4.7	4.1	5.5	5.5	5.6	5.0	4.3	36.0
38.0				4.2	3.7			5.3	4.5	3.9	5.0	5.1	5.2	4.7	4.1	38.0
40.0				4.0	3.5			4.9	4.3	3.7		4.7	4.8	4.5	3.9	40.0
42.0					3.3				4.1	3.5			4.4	4.3	3.7	42.0
44.0					3.2				3.9	3.4			4.1	4.1	3.5	44.0
46.0										3.2				3.8	3.4	46.0
48.0															3.3	48.0
50.0															3.1	50.0
Reeves	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	Reeves

Working radius (m) / Working radius (m)

Boom length (m)	36.6					39.6					42.7					Boom length (m)
Jib length (m)	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	Jib length (m)
12.0	10.9	10.9				10.9					10.9					12.0
14.0	10.9	10.9	10.9	10.0		10.9	10.9	10.9			10.9	10.9	10.9			14.0
16.0	10.9	10.9	10.9	9.8	7.0	10.9	10.9	10.9	9.8	7.1	10.9	10.9	10.9	9.9	7.1	16.0
18.0	10.9	10.9	10.9	9.6	6.9	10.9	10.9	10.9	9.7	6.9	10.9	10.9	10.9	9.7	6.9	18.0
20.0	10.9	10.9	10.6	9.1	6.7	10.9	10.9	10.9	9.5	6.8	10.9	10.9	10.9	9.6	6.8	20.0
22.0	10.9	10.9	9.7	8.3	6.6	10.9	10.9	10.1	8.7	6.6	10.8	10.9	10.5	9.0	6.7	22.0
24.0	9.7	9.9	9.0	7.7	6.4	9.6	9.8	9.4	8.0	6.5	9.5	9.7	9.8	8.3	6.5	24.0
26.0	8.7	8.8	8.3	7.1	6.3	8.6	8.7	8.7	7.4	6.4	8.4	8.6	8.7	7.7	6.4	26.0
28.0	7.8	7.9	7.8	6.6	5.9	7.7	7.8	7.9	6.9	6.1	7.6	7.7	7.8	7.2	6.3	28.0
30.0	7.0	7.1	7.2	6.2	5.5	6.9	7.0	7.1	6.5	5.7	6.8	6.9	7.0	6.8	5.9	30.0
32.0	6.4	6.5	6.6	5.8	5.1	6.3	6.4	6.5	6.1	5.4	6.1	6.2	6.3	6.4	5.6	32.0
34.0	5.8	5.9	6.0	5.5	4.8	5.7	5.8	5.9	5.8	5.0	5.6	5.7	5.8	5.8	5.2	34.0
36.0	5.3	5.4	5.5	5.2	4.6	5.2	5.3	5.4	5.4	4.8	5.0	5.2	5.2	5.3	5.0	36.0
38.0	4.9	4.9	5.0	4.9	4.3	4.7	4.8	4.9	5.0	4.5	4.6	4.7	4.8	4.9	4.7	38.0
40.0	4.5	4.5	4.6	4.7	4.1	4.3	4.4	4.5	4.6	4.3	4.2	4.3	4.4	4.4	4.5	40.0
42.0		4.2	4.3	4.3	3.9	4.0	4.1	4.1	4.2	4.1	3.8	3.9	4.0	4.1	4.1	42.0
44.0			3.9	4.0	3.7		3.7	3.8	3.9	3.9	3.5	3.6	3.7	3.7	3.8	44.0
46.0				3.7	3.6			3.5	3.6	3.6		3.3	3.4	3.4	3.5	46.0
48.0				3.4	3.4			3.2	3.3	3.3		3.1	3.1	3.2	3.2	48.0
50.0					3.2				3.0	3.1			2.9	2.9	3.0	50.0
52.0										2.9				2.7	2.7	52.0
54.0										2.6				2.5	2.5	54.0
56.0															2.3	56.0
Reeves	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	Reeves

Working radius (m) / Working radius (m)

Note:
Ratings according to EN13000.
Ratings shown in [ ] are determined by the strength of the boom or other structural components.
Lifting capacities may vary depending on hook used or with/without auxiliary sheave.
Please refer rated chart in operator's cabin.

Fixed Jib Lifting Capacities (Without Main Hook Block) (Jib Offset Angle : 10°)

Counterweight: 34.6 t
Carbody Weight: 6.5 t

Unit: metric ton

Boom length (m)	45.7					48.8					51.8					Boom length (m)
Jib length (m)	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	Jib length (m)
14.0	10.9	10.9				10.9	10.9				10.9					14.0
16.0	10.9	10.9	10.9	9.9		10.9	10.9	10.9	10.0		10.9	10.9	10.9			16.0
18.0	10.9	10.9	10.9	9.8	7.0	10.9	10.9	10.9	9.8	7.0	10.9	10.9	10.9	9.8	7.0	18.0
20.0	10.9	10.9	10.9	9.6	6.8	10.9	10.9	10.9	9.6	6.9	10.9	10.9	10.9	9.7	6.9	20.0
22.0	10.6	10.8	10.9	9.3	6.7	10.5	10.7	10.8	9.5	6.8	10.4	10.6	10.7	9.5	6.8	22.0
24.0	9.3	9.5	9.6	8.6	6.6	9.3	9.4	9.5	8.9	6.6	9.1	9.3	9.4	9.2	6.7	24.0
26.0	8.3	8.4	8.5	8.0	6.5	8.2	8.4	8.5	8.3	6.5	8.1	8.2	8.3	8.4	6.6	26.0
28.0	7.4	7.5	7.6	7.5	6.4	7.3	7.4	7.6	7.6	6.4	7.2	7.3	7.4	7.5	6.5	28.0
30.0	6.6	6.8	6.9	6.9	6.2	6.5	6.7	6.8	6.9	6.3	6.4	6.5	6.7	6.7	6.4	30.0
32.0	6.0	6.1	6.2	6.3	5.8	5.9	6.0	6.1	6.2	6.0	5.7	5.9	6.0	6.1	6.1	32.0
34.0	5.4	5.5	5.6	5.7	5.5	5.3	5.4	5.5	5.6	5.6	5.2	5.3	5.4	5.5	5.5	34.0
36.0	4.9	5.0	5.1	5.2	5.2	4.8	4.9	5.0	5.1	5.1	4.7	4.8	4.9	4.9	5.0	36.0
38.0	4.4	4.5	4.6	4.7	4.7	4.3	4.4	4.5	4.6	4.7	4.2	4.3	4.4	4.5	4.5	38.0
40.0	4.0	4.1	4.2	4.3	4.3	3.9	4.0	4.1	4.2	4.2	3.8	3.9	4.0	4.1	4.1	40.0
42.0	3.7	3.8	3.8	3.9	4.0	3.6	3.7	3.8	3.8	3.9	3.4	3.5	3.6	3.7	3.7	42.0
44.0	3.3	3.4	3.5	3.6	3.6	3.2	3.3	3.4	3.5	3.5	3.1	3.2	3.3	3.4	3.4	44.0
46.0	3.1	3.1	3.2	3.3	3.3	3.0	3.0	3.1	3.2	3.2	2.8	2.9	3.0	3.1	3.1	46.0
48.0	2.8	2.9	2.9	3.0	3.1	2.7	2.8	2.8	2.9	3.0	2.5	2.6	2.7	2.8	2.8	48.0
50.0		2.6	2.7	2.8	2.8	2.4	2.5	2.6	2.7	2.7	2.2	2.3	2.4	2.5	2.5	50.0
52.0			2.4	2.5	2.6		2.2	2.3	2.4	2.4	1.9	2.0	2.1	2.2	2.2	52.0
54.0				2.3	2.3			2.0	2.1	2.2		1.8	1.9	1.9	2.0	54.0
56.0				2.0	2.1			1.8	1.9	1.9		1.5	1.6	1.7	1.8	56.0
58.0					1.9				1.7	1.7						58.0
60.0										1.5						60.0
Reeves	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	Reeves

Working radius (m)

Boom length (m)	54.9					57.9					61.0					Boom length (m)
Jib length (m)	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	Jib length (m)
14.0	10.9															14.0
16.0	10.9	10.9	10.9			10.9	10.9				10.9	10.9				16.0
18.0	10.9	10.9	10.9	9.9	7.1	10.9	10.9	10.9	9.9		10.9	10.9	10.9	9.9		18.0
20.0	10.9	10.9	10.9	9.7	6.9	10.9	10.9	10.9	9.8	7.0	10.9	10.8	10.8	9.8	7.0	20.0
22.0	10.3	10.5	10.6	9.6	6.8	10.1	10.3	10.5	9.6	6.8	10.1	10.3	10.4	9.7	6.9	22.0
24.0	9.0	9.2	9.3	9.4	6.7	8.9	9.0	9.2	9.3	6.7	8.8	9.0	9.1	9.2	6.8	24.0
26.0	7.9	8.1	8.2	8.3	6.6	7.8	8.0	8.1	8.2	6.6	7.7	7.9	8.0	8.1	6.7	26.0
28.0	7.0	7.2	7.3	7.4	6.5	6.9	7.0	7.2	7.3	6.5	6.8	7.0	7.1	7.2	6.6	28.0
30.0	6.3	6.4	6.5	6.6	6.4	6.1	6.3	6.4	6.5	6.4	6.1	6.2	6.3	6.4	6.5	30.0
32.0	5.6	5.7	5.8	5.9	6.0	5.4	5.6	5.7	5.8	5.8	5.4	5.5	5.6	5.7	5.8	32.0
34.0	5.0	5.1	5.2	5.3	5.4	4.9	5.0	5.1	5.2	5.2	4.8	4.9	5.0	5.1	5.2	34.0
36.0	4.5	4.6	4.7	4.8	4.9	4.4	4.5	4.6	4.7	4.7	4.3	4.4	4.5	4.6	4.6	36.0
38.0	4.1	4.2	4.3	4.3	4.4	3.9	4.0	4.1	4.2	4.3	3.8	3.9	4.0	4.1	4.2	38.0
40.0	3.6	3.8	3.9	3.9	4.0	3.5	3.6	3.7	3.8	3.8	3.4	3.5	3.6	3.7	3.8	40.0
42.0	3.3	3.4	3.5	3.6	3.6	3.1	3.2	3.3	3.4	3.5	3.0	3.1	3.3	3.3	3.4	42.0
44.0	2.9	3.1	3.1	3.2	3.3	2.7	2.9	3.0	3.1	3.1	2.6	2.7	2.9	3.0	3.0	44.0
46.0	2.6	2.7	2.8	2.9	3.0	2.4	2.5	2.6	2.7	2.8	2.2	2.4	2.5	2.6	2.7	46.0
48.0	2.2	2.4	2.5	2.6	2.6	2.0	2.2	2.3	2.4	2.4	1.9	2.1	2.2	2.3	2.3	48.0
50.0	2.0	2.1	2.2	2.3	2.3	1.7	1.9	2.0	2.1	2.1	1.6	1.8	1.9	2.0	2.0	50.0
52.0	1.7	1.8	1.9	2.0	2.1		1.6	1.7	1.8	1.8			1.6	1.7	1.7	52.0
54.0		1.6	1.7	1.7	1.8				1.5	1.6						54.0
56.0				1.5	1.6											56.0
Reeves	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	Reeves

Working radius (m)

Note:
Ratings according to EN13000.
Ratings shown in [ ] are determined by the strength of the boom or other structural components.
Lifting capacities may vary depending on hook used or with/without auxiliary sheave.
Please refer rated chart in operator's cabin.

Fixed Jib Lifting Capacities (Without Main Hook Block) (Jib Offset Angle : 30°)

Counterweight: 34.6 t
Carbody Weight: 6.5 t

Unit: metric ton

Working radius (m)	Boom length (m)	27.4					30.5					33.5					Boom length (m)	Working radius (m)
	Jib length (m)	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	Jib length (m)	
	12.0	9.5															12.0	
	14.0	9.5	7.0				9.5					9.5					14.0	
	16.0	9.5	7.0	5.2			9.5	7.0				9.5	7.0				16.0	
	18.0	9.5	7.0	5.2	4.2		9.5	7.0	5.2			9.5	7.0	5.2			18.0	
	20.0	9.5	7.0	5.2	4.2	4.2	9.5	7.0	5.2	4.2		9.5	7.0	5.2	4.2		20.0	
	22.0	9.1	6.7	5.2	4.2	4.0	9.4	6.9	5.2	4.2	4.1	9.5	7.0	5.2	4.2	4.1	22.0	
	24.0	8.6	6.4	5.1	4.2	3.7	8.9	6.5	5.2	4.2	3.8	9.2	6.7	5.2	4.2	3.9	24.0	
	26.0		6.1	4.9	4.1	3.5	8.6	6.3	5.0	4.2	3.6	8.8	6.4	5.1	4.2	3.7	26.0	
	28.0		5.8	4.6	3.9	3.3	8.2	6.0	4.8	4.0	3.4	8.1	6.2	4.9	4.1	3.5	28.0	
	30.0			4.5	3.7	3.2		5.8	4.6	3.8	3.3	7.3	6.0	4.7	3.9	3.3	30.0	
	32.0			4.3	3.6	3.0			4.4	3.7	3.1		5.8	4.5	3.8	3.2	32.0	
	34.0				3.4	2.9				3.5	3.0			4.4	3.6	3.1	34.0	
	36.0					2.8				3.4	2.9				3.5	3.0	36.0	
	38.0					2.7					2.8				3.4	2.9	38.0	
	40.0															2.8	40.0	
	Reeves	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	Reeves	

Working radius (m)	Boom length (m)	36.6					39.6					42.7					Boom length (m)	Working radius (m)
	Jib length (m)	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	Jib length (m)	
	14.0	9.5					9.5										14.0	
	16.0	9.5	7.0				9.5	7.0				9.5					16.0	
	18.0	9.5	7.0	5.2			9.5	7.0	5.2			9.5	7.0				18.0	
	20.0	9.5	7.0	5.2	4.2		9.5	7.0	5.2	4.2		9.5	7.0	5.2			20.0	
	22.0	9.5	7.0	5.2	4.2	4.2	9.5	7.0	5.2	4.2	4.2	9.5	7.0	5.2	4.2		22.0	
	24.0	9.5	6.9	5.2	4.2	4.0	9.5	7.0	5.2	4.2	4.0	9.5	7.0	5.2	4.2	4.1	24.0	
	26.0	8.9	6.6	5.2	4.2	3.8	8.8	6.7	5.2	4.2	3.8	8.7	6.9	5.2	4.2	3.9	26.0	
	28.0	8.0	6.3	5.0	4.2	3.6	7.9	6.5	5.1	4.2	3.6	7.8	6.6	5.2	4.2	3.7	28.0	
	30.0	7.2	6.1	4.8	4.0	3.4	7.1	6.3	4.9	4.1	3.5	7.0	6.4	5.0	4.2	3.6	30.0	
	32.0	6.5	5.9	4.7	3.8	3.3	6.4	6.1	4.8	3.9	3.3	6.3	6.2	4.9	4.0	3.4	32.0	
	34.0		5.7	4.5	3.7	3.1		5.9	4.6	3.8	3.2	5.7	5.9	4.7	3.9	3.3	34.0	
	36.0			4.4	3.6	3.0		5.4	4.5	3.7	3.1	5.2	5.3	4.6	3.7	3.2	36.0	
	38.0			4.2	3.5	2.9			4.3	3.5	3.0		4.9	4.4	3.6	3.1	38.0	
	40.0				3.4	2.8				3.4	2.9			4.3	3.5	3.0	40.0	
	42.0					2.7				3.4	2.8				3.4	2.9	42.0	
	44.0					2.7					2.7				3.3	2.8	44.0	
	46.0															2.7	46.0	
	Reeves	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	Reeves	

Note:
Ratings according to EN13000.
Ratings shown in [ ] are determined by the strength of the boom or other structural components.
Lifting capacities may vary depending on hook used or with/without auxiliary sheave.
Please refer rated chart in operator's cabin.

Fixed Jib Lifting Capacities (Without Main Hook Block) (Jib Offset Angle : 30°)

Counterweight: 34.6 t
Carbody Weight: 6.5 t

Unit: metric ton

Boom length (m)	45.7					48.8					51.8					Boom length (m)
Jib length (m)	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	Jib length (m)
16.0	9.5					9.5					9.5					16.0
18.0	9.5	7.0				9.5	7.0				9.5	7.0				18.0
20.0	9.5	7.0	5.2			9.5	7.0	5.2			9.5	7.0	5.2			20.0
22.0	9.5	7.0	5.2	4.2		9.5	7.0	5.2	4.2		9.5	7.0	5.2	4.2		22.0
24.0	9.5	7.0	5.2	4.2	4.1	9.5	7.0	5.2	4.2	4.2	9.5	7.0	5.2	4.2	4.2	24.0
26.0	8.6	7.0	5.2	4.2	3.9	8.5	7.0	5.2	4.2	4.0	8.4	7.0	5.2	4.2	4.0	26.0
28.0	7.6	6.8	5.2	4.2	3.8	7.6	6.9	5.2	4.2	3.8	7.4	7.0	5.2	4.2	3.9	28.0
30.0	6.8	6.5	5.1	4.2	3.6	6.8	6.7	5.2	4.2	3.7	6.7	6.8	5.2	4.2	3.7	30.0
32.0	6.1	6.3	5.0	4.1	3.5	6.1	6.3	5.0	4.1	3.5	6.0	6.2	5.1	4.2	3.6	32.0
34.0	5.5	5.7	4.8	3.9	3.3	5.5	5.7	4.9	4.0	3.4	5.4	5.6	5.0	4.1	3.4	34.0
36.0	5.0	5.2	4.7	3.8	3.2	4.9	5.1	4.7	3.9	3.3	4.8	5.0	4.8	3.9	3.3	36.0
38.0	4.6	4.7	4.5	3.7	3.1	4.5	4.6	4.6	3.8	3.2	4.4	4.5	4.7	3.8	3.2	38.0
40.0			4.4	3.6	3.0		4.2	4.4	3.7	3.1	3.9	4.1	4.2	3.7	3.1	40.0
42.0			4.0	3.5	2.9		3.8	4.0	3.6	3.0		3.7	3.9	3.6	3.0	42.0
44.0				3.4	2.8			3.6	3.5	2.9		3.4	3.5	3.5	2.9	44.0
46.0					2.8				3.4	2.8			3.2	3.3	2.9	46.0
48.0					2.7				3.1	2.7				3.0	2.8	48.0
50.0					2.6					2.7				2.7	2.7	50.0
52.0															2.5	52.0
Reeves	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	Reeves

Working radius (m)

Boom length (m)	54.9					57.9					61.0					Boom length (m)
Jib length (m)	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	9.1	12.2	15.2	18.3	21.3	Jib length (m)
18.0	9.5					9.5					9.5					18.0
20.0	9.5	7.0				9.5	7.0				9.5	7.0				20.0
22.0	9.5	7.0	5.2			9.5	7.0	5.2			9.5	7.0	5.2			22.0
24.0	9.4	7.0	5.2	4.2		9.3	7.0	5.2	4.2		9.2	7.0	5.2	4.2		24.0
26.0	8.3	7.0	5.2	4.2	4.1	8.1	7.0	5.2	4.2	4.1	8.1	7.0	5.2	4.2	4.1	26.0
28.0	7.3	7.0	5.2	4.2	3.9	7.2	7.0	5.2	4.2	4.0	7.1	7.0	5.2	4.2	4.0	28.0
30.0	6.5	6.8	5.2	4.2	3.8	6.4	6.6	5.2	4.2	3.8	6.3	6.6	5.2	4.2	3.8	30.0
32.0	5.8	6.0	5.2	4.2	3.6	5.7	5.9	5.2	4.2	3.7	5.6	5.9	5.2	4.2	3.7	32.0
34.0	5.2	5.4	5.0	4.1	3.5	5.1	5.3	5.1	4.2	3.5	5.0	5.3	5.2	4.2	3.6	34.0
36.0	4.7	4.9	4.9	4.0	3.4	4.6	4.8	4.9	4.1	3.4	4.5	4.7	4.9	4.1	3.5	36.0
38.0	4.2	4.4	4.6	3.9	3.3	4.1	4.3	4.4	3.9	3.3	4.0	4.2	4.4	4.0	3.4	38.0
40.0	3.8	4.0	4.1	3.8	3.2	3.7	3.8	4.0	3.8	3.2	3.6	3.8	3.9	3.9	3.3	40.0
42.0	3.4	3.6	3.7	3.7	3.1	3.3	3.4	3.6	3.7	3.1	3.2	3.4	3.5	3.7	3.2	42.0
44.0	3.1	3.2	3.4	3.5	3.0	2.9	3.1	3.2	3.4	3.0	2.8	3.0	3.2	3.3	3.1	44.0
46.0			3.0	3.2	2.9		2.7	2.9	3.0	3.0	2.4	2.6	2.8	3.0	3.0	46.0
48.0			2.7	2.9	2.8			2.6	2.7	2.9		2.3	2.5	2.6	2.8	48.0
50.0				2.6	2.7			2.2	2.4	2.5		2.0	2.1	2.3	2.4	50.0
52.0					2.4				2.1	2.2			1.8	2.0	2.1	52.0
54.0					2.1					1.9				1.7	1.8	54.0
56.0										1.7					1.6	56.0
Reeves	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	Reeves

Working radius (m)

Note:
Ratings according to EN13000.
Ratings shown in [ ] are determined by the strength of the boom or other structural components.
Lifting capacities may vary depending on hook used or with/without auxiliary sheave.
Please refer rated chart in operator's cabin.

SUPPLEMENTAL DATA FOR CLAMSHELL RATING CHART

- Operating radius is the horizontal distance from centerline of rotation to a vertical line through the center of gravity of the load.
- Deduct weight of bucket, slings and all other load handling accessories from main boom ratings shown.
- Ratings shown are based on freely suspended loads and make no allowance for such factors as wind effect on lifted load, ground conditions, out-of-level, operating speeds or any other condition that could be detrimental to the safe operation of this equipment. The operator, therefore, has the responsibility to judge the existing conditions and reduce lifted loads and operating speeds accordingly.
- Rated loads do not exceed 66% of minimum tipping loads.
- Ratings are for operation on a firm and level surface, up to 1% gradient.
- At radii and boom lengths where no ratings are shown on chart, operation is not intended nor approved.
- Boom inserts and guy lines must be arranged as shown in the "operator's manual".
- Boom hoist reeving is 10 part line.
- Gantry must be in raised position for all conditions.
- Boom backstops are required for all boom lengths.
- The boom should be erected over the front of the crawlers, not laterally.
- Crawler frames must be fully extended for all crane operations.

(Clamshell bucket lifting)

- The total load that can be lifted is the value for weight of bucket, slings, and all other load handling accessories deducted from main boom ratings shown.
- The weight of bucket and materials must not exceed rated load.
- Optimum bucket should be required according to material.
- Bucket capacity (m^3) x specified gravity of material (ton/m^3) + bucket weight (ton) = rated load.
- Bucket weight must also be decreased according to operating cycle and bucket lowering height.
- Rated loads are determined by stability and boom strength. During simultaneous operations of boom and swing, rapid acceleration or deceleration must be avoided.
- Do not attempt to cast the bucket while swinging or diagonal draw-cutting.

<Reference Information>

Main hoist loads

No. of Parts of Line	1
Maximum Loads (kN)	98
Maximum Loads (t)	10.0

Assembling the counterweight



Operation of this equipment in excess of rated loads or disregard of instruction voids the warranty.

Clamshell Rating Charts
Crane Boom Capacities

Counterweight: 23.1 t
Without Carbody Weight
Crawler Fully Extended
Unit: metric ton

Load radius (m) \ Boom length (m)	15.2	18.3	21.3	24.4					Boom length (m) \ Load radius (m)
7.0	10.0								**7.0**
8.0	10.0	10.0							**8.0**
9.0	10.0	10.0	10.0						**9.0**
10.0	10.0	10.0	10.0	9.4					**10.0**
11.0	10.0	10.0	10.0	9.3					**11.0**
12.0	10.0	10.0	10.0	9.3					**12.0**
13.0	10.0	10.0	10.0	9.3					**13.0**
14.0	10.0	10.0	10.0	9.3					**14.0**
15.0		10.0	10.0	9.3					**15.0**
16.0		9.8	9.9	9.0					**16.0**
17.0			9.3	8.8					**17.0**
18.0			8.6	8.6					**18.0**
19.0			7.9	8.2					**19.0**
20.0				7.6					**20.0**
21.0				7.1					**21.0**
22.0									**22.0**
23.0									**23.0**
24.0									**24.0**
25.0									**25.0**
26.0									**26.0**
27.0									**27.0**
28.0									**28.0**
29.0									**29.0**
30.0									**30.0**
31.0									**31.0**
32.0									**32.0**
33.0									**33.0**
Reeves	1	1	1	1					**Reeves**

Note:
Please refer rated chart in operator's cabin.

SUPPLEMENTAL DATA FOR REDUCED WEIGHTS RATING CHART

- Ratings according to EN13000.
- Operating radius is the horizontal distance from centerline of rotation to a vertical line through the center of gravity of the load.
- Deduct weight of hook block (s), slings and all other load handling accessories from main boom ratings shown.
- Ratings shown are based on freely suspended loads and make no allowance for such factors as wind effect on lifted load, ground conditions, out-of-level, operating speeds or any other condition that could be detrimental to the safe operation of this equipment. The operator, therefore, has the responsibility to judge the existing conditions and reduce lifted loads and operating speeds accordingly.
- Ratings are for operation on a firm and level surface, up to 1% gradient.
- At radii and boom lengths where no ratings are shown on chart, operation is not intended nor approved.
- Boom inserts and guy lines must be arranged as shown in the "operator's manual".
- Boom hoist reeving is 10 part line.
- Gantry must be in raised position for all conditions.
- Boom backstops are required for all boom lengths.
- The boom should be erected over the front of the crawlers, not laterally.
- Ratings inside of boxes ☐ are limited by strength of materials.
- The minimum rated load is 1.5 (ton).
- Crawler frames must be fully extended for all crane operations.

(Crane boom lifting)

- The total load that can be lifted is the value for weight of hook block, slings, and all other load handling accessories deducted from main boom ratings shown.

Counterweight	Carbody weight	Boom lenght	
		Without aux.	With aux.
23.1 ton	Without	15.2 m ~ 57.9 m	15.2 m ~ 54.9 m

Assembling the counterweight

23.1 ton counterweight
without carbody weight



<Reference Information>

Main hoist loads

No. of Parts of Line	1	2	3	4	5
Maximum Loads (kN)	108	216	324	431	539
Maximum Loads (t)	11.0	22.0	33.0	44.0	55.0

No. of Parts of Line	6	7	8	9	10
Maximum Loads (kN)	647	755	863	971	1,079
Maximum Loads (t)	66.0	77.0	88.0	99.0	110.0

Auxiliary hoist loads

No. of Parts of Line	1	2
Maximum Loads (kN)	108	216
Maximum Loads (t)	11.0	22.0

Weight of hook block				
Hook Block	110 t	70 t	35 t	Ball Hook
Weight (t)	1.7	0.9	0.7	0.45

Operation of this equipment in excess of rated loads or disregard of instruction voids the warranty.

Reduced Weights Rating Charts
Crane Boom Lifting Capacities

Counterweight: 23.1 t
Without Carbody Weight
Crawler Fully Extended
Unit: metric ton

Working radius (m) \ Boom length (m)	15.2	18.3	21.3	24.4	27.4	30.5	33.5	36.6	39.6	42.7	Boom length (m) \ Working radius (m)
3.5	3.6m/94.2										3.5
4.0	85.3	4.1m/83.3									4.0
4.5	76.2	75.7	4.6m/69.2								4.5
5.0	68.9	66.0	62.3	59.1							5.0
5.5	58.9	58.4	55.5	52.8	5.5m/50.4	5.9m/44.6					5.5
6.0	50.8	50.4	49.9	47.8	45.7	43.8	6.4m/39.2	6.8m/35.4			6.0
7.0	39.6	39.3	39.0	38.7	38.4	37.0	35.6	34.4	7.3m/31.7	7.8m/28.6	7.0
8.0	32.3	32.3	32.2	32.1	32.0	31.9	30.8	29.9	28.8	27.9	8.0
9.0	27.2	27.2	27.2	27.2	27.2	27.1	27.0	26.3	25.4	24.7	9.0
10.0	23.5	23.5	23.5	23.5	23.4	23.3	23.2	23.2	22.7	22.0	10.0
12.0	18.2	18.2	18.2	18.2	18.1	18.0	18.0	17.9	17.9	17.7	12.0
14.0	14.8	14.8	14.8	14.8	14.7	14.6	14.5	14.4	14.4	14.2	14.0
16.0	14.4m/14.3	12.5	12.4	12.3	12.2	12.1	12.0	12.0	11.9	11.8	16.0
18.0		17.1m/11.5	10.6	10.5	10.4	10.3	10.2	10.1	10.0	9.9	18.0
20.0			19.7m/9.4	9.1	9.0	8.9	8.7	8.7	8.6	8.5	20.0
22.0				8.0	7.9	7.7	7.6	7.6	7.5	7.4	22.0
24.0				22.4m/7.8	7.0	6.8	6.7	6.7	6.6	6.4	24.0
26.0					25.0m/6.5	6.1	5.9	5.9	5.8	5.7	26.0
28.0						27.6m/5.6	5.3	5.3	5.1	5.0	28.0
30.0							4.8	4.7	4.6	4.5	30.0
32.0							30.3m/4.6	4.3	4.1	4.0	32.0
34.0								32.9m/4.1	3.7	3.5	34.0
36.0									35.6m/3.3	3.1	36.0
38.0										2.8	38.0
40.0										38.2m/2.6	40.0
42.0											42.0
44.0											44.0
Reeves	10	8	7	6	5	5	4	4	3	3	Reeves

Working radius (m) \ Boom length (m)	45.7	48.8	51.8	54.9	57.9						Boom length (m) \ Working radius (m)
8.0	8.2m/26.3	8.7m/24.0									8.0
9.0	23.9	23.2	9.1m/22.2	9.6m/20.3							9.0
10.0	21.3	20.8	20.1	19.5	18.9						10.0
12.0	17.4	17.0	16.5	16.0	15.5						12.0
14.0	14.1	14.0	13.8	13.4	13.0						14.0
16.0	11.6	11.6	11.4	11.4	11.0						16.0
18.0	9.8	9.7	9.6	9.6	9.4						18.0
20.0	8.3	8.3	8.1	8.1	8.0						20.0
22.0	7.2	7.1	7.0	7.0	6.8						22.0
24.0	6.3	6.2	6.1	6.0	5.9						24.0
26.0	5.5	5.4	5.3	5.3	5.1						26.0
28.0	4.9	4.8	4.6	4.6	4.5						28.0
30.0	4.3	4.2	4.1	4.0	3.8						30.0
32.0	3.8	3.7	3.5	3.5	3.3						32.0
34.0	3.3	3.3	3.1	3.0	2.8						34.0
36.0	2.9	2.9	2.7	2.6	2.4						36.0
38.0	2.6	2.5	2.3	2.2	2.1						38.0
40.0	2.2	2.2	2.0	1.9	1.7						40.0
42.0	40.8m/2.1	1.9	1.7	1.6							42.0
44.0		43.5m/1.6									44.0
46.0											46.0
48.0											48.0
50.0											50.0
52.0											52.0
54.0											54.0
56.0											56.0
58.0											58.0
Reeves	3	3	3	2	2						Reeves

Note:
Ratings according to EN13000.
Ratings shown in [ ] are determined by the strength of the boom or other structural components.
Lifting capacities may vary depending on hook used or with/without auxiliary sheave.
Please refer rated chart in operator's cabin.

SUPPLEMENTAL DATA FOR BARGE RATING CHART

- Operating radius is the horizontal distance from centerline of rotation to a vertical line through the center of gravity of the load.
- Deduct weight of hook block (s), slings and all other load handling accessories from main boom ratings shown.
- Condition of barge stability this rating chart were determined under the condition below. The stability of barge shall meet below condition. During operation the machinery static inclination against horizontal level.

(A) Both sides (right & left) of machine
Maximum inclination shall be within 1.5 degrees

(B) Front & backward of macine
Maximum inclination shall be within 3.0 degrees



(A)



(B)



- Working area shall be inshore and smooth water.
- Applicable regulations for structure japanese construction codes for mobile crane
  ※Regulation of class of shipping (abs, lloyd, bv, nk, etc) are not adapted.
- At radii and boom lengths where no ratings are shown on chart, operation is not intended nor approved.
- Boom inserts and guy lines must be arranged as shown in the "operator's manual".
- Boom hoist reeving is 10 part line.
- Gantry must be in raised position for all conditions.
- Boom backstops are required for all boom lengths.
- The boom should be erected over the front of the crawlers, not laterally.
- Ratings inside of boxes ▭ are limited by strength of materials.
- The minimum rated load is 1.5 (ton).
- Crawler frames must be fully extended for all crane operations.
- The machinery should be fastened to the deck of the barge to prevent tip over and sliding.
- Towing area
  Towing area shall be within coastal area and quiet wave condition. Offshore and open sea is not considered for this machinery. Depend on the height of wave, counterweight shall be reduced during towing.

(Crane boom lifting)

- The total load that can be lifted is the value for weight of hook block, slings, and all other load handling accessories deducted from main boom ratings shown.

<Reference Information>

Main hoist loads

No. of Parts of Line	1	2	3	4	5
Maximum Loads (kN)	108	216	324	431	539
Maximum Loads (t)	11.0	22.0	33.0	44.0	55.0

No. of Parts of Line	6
Maximum Loads (kN)	618
Maximum Loads (t)	63.0

Auxiliary hoist loads

No. of Parts of Line	1	2
Maximum Loads (kN)	108	216
Maximum Loads (t)	11.0	22.0

Weight of Hook Block				
Hook Block	110 t	70 t	35 t	Ball Hook
Weight (t)	1.7	0.9	0.7	0.45

Operation of this equipment in excess of rated loads or disregard of instruction voids the warranty.

Barge Raiting Chart
Crane Boom Lifting Capacities

Counterweight: 34.6 t
Carbody Weight: 6.5 t
Crawler Fully Extended
Unit: metric tons

Load radius (m) \ Boom length (m)	15.2	18.3	21.3	24.4	27.4	30.5	33.5	36.6	Boom length (m) \ Load radius (m)
5.0	63.0	5.5m/54.4							**5.0**
6.0	52.8	52.6	6.2m/46.4	6.9m/39.9					**6.0**
7.0	44.5	44.3	44.2	39.7	7.6m/35.1				**7.0**
8.0	37.7	37.5	37.4	37.0	34.5	7.6m/30.8			**8.0**
9.0	32.4	32.3	32.2	31.9	31.7	29.9	27.4	9.6m/24.9	**9.0**
10.0	28.3	28.2	28.0	28.0	27.9	27.8	26.5	24.5	**10.0**
12.0	21.4	22.0	21.9	21.8	21.7	21.6	21.5	21.4	**12.0**
14.0	16.3	17.2	17.7	18.0	17.9	17.8	17.7	17.6	**14.0**
16.0	14.4m/15.3	13.5	14.0	14.9	15.3	15.2	15.1	15.0	**16.0**
18.0		17.1m/11.9	11.3	12.2	12.8	13.2	13.1	13.0	**18.0**
20.0			19.7m/9.5	10.1	10.7	11.2	11.5	11.4	**20.0**
22.0				8.4	9.0	9.5	9.8	10.0	**22.0**
24.0				22.4m/8.1	7.6	8.1	8.4	8.7	**24.0**
26.0					25.0m/7.0	6.9	7.2	7.6	**26.0**
28.0						27.6m/6.0	6.2	6.6	**28.0**
30.0							5.4	5.7	**30.0**
32.0							30.3m/5.3	5.0	**32.0**
34.0								32.9m/4.7	**34.0**
Reeves	6	5	5	4	4	3	3	3	**Reeves**

Note:
Ratings according to japanese construction codes for mobile cranes and japanese safety ordinance on cranes, etc.
Ratings shown in [ ] are determined by the strength of the boom or other structual components.
Lifting capacities may vary depending on hook used or with/without auxiliary sheave.
Please refer rated chart in operator's cabin.

TRANSPORTATION PLAN

Name	Dimension	Weight (kg)
Base Machine • Boom base • Gantry • Crawler • Wire rope (Front / rear / boom hoist)		57,410
Base Machine • Gantry • Crawler • Wire rope (Front / rear / boom hoist)		54,090
Base Machine • Boom base • Gantry • Wire rope (Front / rear / boom hoist) • Without crawler		33,550
Base Machine • Gantry • Wire rope (Front / rear / boom hoist) • Without crawler		30,230
Crawler		11,930

PARTS AND ATTACHMENTS

Base Machine
Boom base, Gantry, Crawler, Wire rope (Front/rear/boom hoist)
Weight: 57,410 kg Width: 3,500 mm



Crawler
Weight: 11,930 kg



Translifter
Weight: 320 kg / 1 piece



Backstop
Weight: 440 kg



Jib Tip
Weight: 280 kg



Jib Base
Weight: 200 kg



3.0 m Jib Insert
Weight: 100 kg



6.0 m Jib Insert
Weight: 180 kg



Strut
Weight: 250 kg



Auxiliary Sheave
Weight: 300 kg



Counterweight No.1
Weight: 11,600 kg



Counterweight No.3, No.5 (R)
Weight: 5,750 kg



Counterweight No.2, No.4 (L)
Weight: 5,750 kg



Carbody Weight (With float)
Weight: 3,320 kg / 1 piece



Carbody Weight (Without float)
Weight: 3,250 kg / 1 piece



Self Removal Unit
Weight: 870 kg



Boom Tip
Weight: 1,525 kg



Boom Base
Weight: 2,235 kg



3.0 m
Boom Insert
Weight: 380 kg



6.1 m
Boom Insert
Weight: 655 kg



12.2 m
Boom Insert
Weight: 1,195 kg



12.2 m
Boom Insert (with Lug)
Weight: 1,220 kg



Gantry
Weight: 1,320 kg



Upper Spreader
Weight: 300 kg



Lower Spreader
Weight: 200 kg



Ball Hook
Weight: 450 kg



35 t Hook
Weight: 700 kg



70 t Hook
Weight: 900 kg



110 t Hook
Weight: 1,700 kg



Note: This catalog may contain photographs of machines with specifications, attachments and optional equipment not certified for operation in your country. Please consult KOBELCO for those items you may require. Due to our policy of continual product improvements all designs and specifications are subject to change without advance notice.

KOBELCO CRANES CO., LTD.

17-1, Higashigotanda 2-chome, Shinagawa-ku,Tokyo 141-8626 JAPAN
Tel: +81-3-5789-2130 Fax: +81-3-5789-3372
URL: http://www.kobelco-cranes.com/

Inquiries To:

Bulletin No. CKS1100-SPEC-NR1